


# STANDARD NOTES FOR TELEPHONE INSTALLATION

1. SANDWICH ISLES COMMUNICATIONS (SIC) WILL LOCATE IT'S EQUIPMENT ENCLOSURE A MINIMUM OF 2'-0" FROM THE ELECTRIC POWER METER. HOMEOWNER/DEVELOPER MUST ENSURE THAT SUFFICIENT CLEAR SPACE IS ALLOWED FOR SIC TO MOUNT IT'S ENCLOSURE.

2. THE HOMEOWNER/DEVELOPER IS RESPONSIBLE FOR THE INSTALLATION OF TELEPHONE RJ-11 JACKS AND WIRING INSIDE THE HOUSE. INSIDE WIRING (IW) SHOULD BE 4-PAIR CATEGORY 5 WIRE HOMERUN FROM EACH JACK TO THE SIC ENCLOSURE. LEAVE AT LEAST 3 FT. OF SLACK AT THE ENCLOSURE. THE CONTRACTOR WILL TERMINATE THE IW TO SIC'S EQUIPMENT. THE HOMEOWNER/DEVELOPER IS RESPONSIBLE FOR INSTALLATION OF CATV CABLE INSIDE THE HOUSE. FOR CATV INSTALLATION SPECIFICATIONS CONTACT OCEANIC CABLE COMPANY. LEAVE AT LEAST 4 FT. SLACK CATV CABLE AT OCEANIC ENCLOSURE.

3. THE HOMEOWNER/DEVELOPER SHALL PROVIDE A 15 AMP CIRCUIT AND ELECTRICAL CONDUCTOR AT THE INDICATED LOCATION. THE CIRCUIT SHOULD BE DEDICATED TO SIC SERVICE AND LABELED AT THE CIRCUIT BREAKER PANEL.



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION AND CONSTRUCTION OF THIS PROJECT WILL BE UNDER MY OBSERVATION

*Michael A. Riley* 3/2012  
Signature License Expiration Date

3/4/10	REVISED ELEC.	MSC
DATE	DESCRIPTION	BY

SIC TELCOM RESIDENTIAL  
INSTALLATION  
SCALE: NTS



Sandwich Isles  
Communications, Inc.

A Waimana Company